## **Revisions are shown in red.**

## Solution 533, p. 96:

Line 4 should read as follows:

Allowable load = 2(13)(0.79) = 21.2 kips

Previously posted errata continued on next page

#### **Revisions are shown in red.**

#### Question 509, p. 38:

Question 509 should read as follows:

A double-tee supported by an L-beam is loaded as shown in the figure.

#### Design Code:

ACI 318: Building Code Requirements for Structural Concrete, 2011.

The magnitude of the ultimate torsion (ft-kips) induced into the L-beam, by superimposed dead and live load applied on the double-tee, is most nearly:

- (A) 18.7
- (B) 21.4
- (C) 28.6
- (D) 32.8



NOT TO SCALE

#### Solution 509, p. 87:

Solution 509 should read as follows:

15.5 in. - 6 in. = 9.5 in.  $W_{u/DT} = [1.2(10 \text{ psf}) + 1.6(50 \text{ psf})]15 \text{ ft} = 1,380 \text{ plf}$   $R_{u/DT} = \frac{1}{2}(1.38 \text{ klf})(60 \text{ ft}) = 41.4 \text{ kips}$  $T_u = 41.4 \text{ kips} \left(\frac{9.5 \text{ in.}}{12 \text{ in./ft}}\right) = 32.8 \text{ ft-kips}$ 

#### THE CORRECT ANSWER IS: (D)



#### Question 513, p. 41:

Question 513 should read as follows: The pipe member shown in the figure has a constant section and the following properties:

Outside diameter	10 in.
Moment of inertia	90 in <sup>4</sup>
Area	7 in <sup>2</sup>

Neglecting the weight of the pipe, the maximum compressive stress (ksi) at the support is most nearly:



#### Solution 513, p. 88:

Solution 513 should read as follows:

$$\begin{split} M_{S} &= (20 \text{ kips})(12 \text{ in.} - 5 \text{ in.}) = 140 \text{ in.-kips} \\ N_{S} &= 20 \text{ kips} \\ \sigma_{flexure} &= \frac{(140 \text{ in.-kips})(5 \text{ in.})}{90 \text{ in}^{4}} = 7.8 \text{ ksi} \begin{cases} \text{Top tension} \\ \text{Bottom compression} \end{cases} \\ \sigma_{axial} &= \frac{20 \text{ kips}}{7 \text{ in}^{2}} = 2.9 \text{ ksi tension} \\ \text{Max compressive stress (at bottom):} \\ -7.8 \text{ ksi} + 2.9 \text{ ksi} = -4.9 \text{ ksi} \end{cases}$$

#### THE CORRECT ANSWER IS: (B)

# Solution 520, p. 91:

Line 2 should read as follows:

Two or more spans not exceeding 10 ft

# Question 528, p. 52:

Question 528 should read as follows:

A connection is shown in the figure.

Design Code: AISC: *Steel Construction Manual*, 14th edition.

Material:

A36 steel

Assumptions:

The bolt is sufficient. The concrete is sufficient. The load P is equally distributed along the entire 6-in.-long angle.

The maximum load P (ASD) or  $\phi P_n$  (LRFD) in kips that can be carried by the angle is most nearly:

	ASD	<b>LRFD</b>
(A)	0.8	1.2
(B)	1.1	1.7
(C)	1.2	1.8
(D)	2.0	2.0



#### Solution 528, p. 94:

Solution 528 should read as follows:

By inspection P controls.

$$\begin{split} M_n &= M_p = F_y Z_x \le 1.6 \ M_y \\ F_y &= 36 \ ksi \\ S_x &= 1/6 \ bd^2 = 1/6 \ (6)(0.375)^2 = 0.141 \ in^3 \\ M_y &= F_y S_x = (36)(0.141) = 5.076 \ in.-kips \\ Z_x &= 1/4 \ bd^2 = 1/4 \ (6)(0.375)^2 = 0.211 \ in^3 \\ M_p &= F_y Z_x = (36)(0.211) = 7.6 \ in.-kips \quad \leftarrow \text{governs} \\ \text{Check } M_p \le 1.6 \ M_y \qquad 1.6 \ (5.076) = 8.1 > 7.6 \ \therefore \ \text{OK} \end{split}$$

AISC ASD:  $M_n/\Omega = 7.6/1.67 = 4.55 \text{ in.-kips}$  $P_{\text{allow}} = \frac{4.55}{\left[4 - (1/2)(3/8)\right]} = 1.19 \sim 1.2$ 

AISC LRFD:  $\phi M_n = 0.9(7.6) = 6.84 \text{ in.-kips}$  $\phi P_n = \frac{6.84}{\left[4 - (1/2)(3/8)\right]} = 1.79 \sim 1.8$ 

THE CORRECT ANSWER IS: (C)

Previously posted errata continued on next page

## ERRATA for PE Civil Structural Practice Exam ISBN 978-1-932613-72-8 Copyright 2014 (October 2014 First Printing) Errata posted 5-7-2015

#### **Revisions are shown in red.**

# Solution 538, p. 98:

Solution 538 should read as follows:

Reference: AASHTO Section 9.7.2.3.

AASHTO prescriptively calls out to add back a single flange overhang (not one on each side).

 $\begin{array}{ll} L_{eff} &= 8.5 \ ft - b_f + flange \ overhang \\ &= 8.5 \ ft - 1.5 \ ft + 0.25 \ ft \end{array}$ 

= 7.25 ft (7 ft 3in.)

## THE CORRECT ANSWER IS: (C)